

# THE CONSTRUCTION OF THE CAVERNS IN THE GAS STORAGE PROJECT LL. TORUP, DENMARK

*by*

Quast, P.

Kavernen Bau- und Betriebs- GmbH

## Summary

The Ll. Torup gas storage facility is the planned equalisation storage of the gas supply system in Denmark. It will consist of in total 6 caverns, with a working volume of around 240 million m<sup>3</sup> ( $V_g$ ). Three caverns are already finished with working volumes of between 350 000 and 500 000 m<sup>3</sup>.

The first 3 caverns are currently undergoing their first fill procedures with natural gas. The three remaining caverns are being leached at present. This presentation will provide a summary of the cavern layout and the solution mining planning as based on the cores investigated and logs.

©2023 – Solution Mining Institute

Full Paper is Available in the SMRI Library([www.solutionmining.org](http://www.solutionmining.org))